

**RENOVATION WORK AT 10TH-14TH FLOOR OF PAKISTAN REINSURANCE COMPANY (PRC)
BUILDING KARACHI**

S.No	Particulars	No	Qty.	Rate (Rs.)	Amount
1	Switch , SP , socket outlet 3 pin , 15A, shuttered pattern, mounted in Bakelite box complete , supply and fixing	Each	300		
2	Switch , SP , socket outlet 3 pin , 20A, for AC shuttered pattern, mounted in Bakelite box complete , supply and fixing	Each	35		
3	Switch , SP , socket outlet 3 pin , 32A, for AC shuttered pattern, mounted in Bakelite box complete , supply and fixing	Each	4		
4	Wiring For 15 Amps Socket from D.B. Wiring of 15 Amps socket outlet with 4.0 Sq.mm PVC insulated single core copper conductor cable with 2.5sq.mm earth wire.(Pakistan cable or approved equivalent)	Meter	1700		
5	Wiring For 20 Amps Socket (AC) from D.B. Wiring of 20 Amps socket outlet with 4.0 Sq.mm PVC insulated single core copper conductor cable with 2.5sq.mm earth wire.(Pakistan cable or approved equivalent)	Meter	700		
6	Wiring For 32 Amps Socket (AC) from D.B. Wiring of 32 Amps socket outlet with 6.0 Sq.mm PVC insulated single core copper conductor cable with 4sq.mm earth wire.(Pakistan cable or approved equivalent)	Meter	150		
7	LIGHTING FIXTURE Supply and installation standard LED panels 36w Philips or equivalent. Including all installation material.	Each	500		
8	Supply and installation down light 12w LED Philips or equivalent. Including all installation material.	Each	400		

Total Cost

-